





SECTION B1 S4
1:20

BASEMENT FLOOR FRAMING PLAN
1:100

1. CONCRETE SLAB TO BE 190 THICK UNLESS NOTED. TEMP 10-300 DROPS 100 DP.
2. CONCRETE TO HAVE A COMPRESSIVE STRENGTH OF 3500 P.S.I. GRADE AT 28 DAYS.
3. REINFORCING STEEL TO HAVE A YIELD STRENGTH OF 60,000 P.S.I.
4. ALL REINFORCING STEEL TO BE 10M BARS UNLESS NOTED.
5. REINFORCING STEEL IN H-S I DIRECTION TO BE PLACED CLOSEST TO TOP AND BOTTOM SURFACES OF CONCRETE.
6. AT LEAST 50% OF TOP STEEL IN COLUMN STRIP TO BE PLACED DIRECTLY OVER COLUMN WITHIN A WIDTH EQUAL TO COLUMN WIDTH + 10" EITHER SIDE OF COLUMN.
7. MAXIMUM SPACING OF REINFORCING BARS TO BE
8. ULTIMATE STRENGTH DESIGN HAS BEEN USED.
9. SEE GENERAL NOTES AND TYPICAL DETAILS ON DRAWING 9-10.

D. LAW CONSULTANTS LIMITED
CONSULTING STRUCTURAL ENGINEERS
30 SCARSDALE RD. - DON MILLS, ONT.

JOB NAME
COMMERCIAL & APT PROJ.
STASH INVEST INC.
254 JARVIS ST TORONTO

SHEET TITLE		SHEET No.	
BASEMENT FLOOR		S 4	
ARCHITECT	SCALE	DATE	
E. I. RICHMOND		MAY 29/80	
DRAWN BY	CHECKED BY		

REVISIONS		
DATE	No.	NOTATION
JUN 9	1ST	ISSUE

